

5-11-88 15-147-00494-00-00

6 040891

API NUMBER 15- 1-17-49

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SEC. 28, T 5 S, R 20 W.

2310 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Vehige A Well # 8

Operator: Cities Service Oil and Gas Corp  
Name & Address: 3545 N.W. 58th Street  
Okla City, Ok. 73112

County Phillips 117.46

Well Total Depth 3614 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205' w/250 sks

Abandoned Oil Well  Gas Well  Input Well  SWD Well  U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Ks.

Company to plug at: Hour: 8:00AM Day: 11 Month: May Year: 19 88

Plugging proposal received from Phillip Pringle

(company name) Cities Service (phone)

were: 5 1/2" casing set at 3614' w/150 sks cement. Perfs at 3554' to 3572'. Perf casing at 1660' and 1050' w/4 SPF.

Ordered 325 sks 65/35 Poz 10% Gel w/1/4# F.C. plus 6 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00PM Day: 11 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 225 sks cement w/1/4# F.C. plus 5 sks

Hulls mixed in cement. Max Psi 1100# Shut in 600#. Pumped in 8 5/8" casing.

75 sks cement w/1/4# F.C. Max Psi 750# Shut in 400#.

RECEIVED  
STATE CORPORATION COMMISSION  
7-6-88  
JUL 6 1988

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Dennis L. Hamel (TECHNICIAN)

DATE 7-7-88  
INV. NO. 21204  
5-11

AUG 3 1988