

4-060648

2-16 15-147-00914-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 6-16-46

NE NW NW /4 SEC. 31, 05 S, 20 W  
4950 feet from S section line  
4290 feet from E section line

Operator license# 5447

Lease Veeh "A" well # 5

Operator: OXY USA, Inc.

County Phillips

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3669 feet <sup>119.24</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 223 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Co Tools License#    

Address:    

Company to plug at: Hour: 9:00A.M. Day: 16 Month: February Year: 95

Plugging proposal received from: J.D. Hininger

Company: OXY USA, Inc. Phone: 913-434-7681

Were: Order 355 sxs. 60/40 posmix - 10% gel and hulls.  
W.L.T.D. past perforations with static water level.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:30A.M., Day: 16, Month: February, Year: 95

Actual plugging report: 8 5/8" to 223' w/175 sxs. 5 1/2" to 3667' w/100  
sxs. R.U. and perforate at 1150' and 1830'. R.U. up cementer.  
Tied onto production casing and pumped 305 sxs. cement with 400# hulls.  
Max. P.S.I. 400#. S.I.P. 50#. Tied onto annulus and pumped 50 sxs.  
with 100# hulls. Max. P.S.I. 200#. S.I.P. 50#.

Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC X, NO     Dakota plug: YES X NO      
Plugged through TUBING    , CASING X. Elevation: 2245 GL    

I did  I did not  observe the plugging.

DATE 3-8-95

INV. NO. 42392

2-16 APR 25 1995

*[Signature]*  
(agent)  
3-6-95

Form CP-2/3

STATE CORPORATION COMMISSION  
RECEIVED  
CONSERVATION DIVISION  
MAR 06 1995