

11-12 4-041824 15-147-00911-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 12-24-41

SW SE NW /4 SEC. 31, 05 S, 20 W
2970 feet from S section line
3630 feet from E section line

Operator license# 5447

Lease: Veeh Well # 1

Operator: OXY USA, Inc.

County: Phillips 118.56

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3648 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 154 feet
w/125 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing, Inc. License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 2:00P.M. Day: 12 Month: November Year: 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3637' w/100 sxs.
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 5:30 P.M., Day: 12, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1150' and 1790' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600' Pumped 65 sxs MIDCON 2 with 2% CC and 300# cottonseed hulls. Pulled 48 joints to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 30 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 15 sxs cement. Max. P.S.I. 500#. S.I.P. 275#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Rig down. Total cement used 225 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC, NO
Plugged through TUBING X, CASING. Elevation: 2222 K.B.
Anhy.plug: YES X NO
Dakota plug: YES X, NO

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
JAN 13 1997
DATE
INV. NO. 47333