

6-18-87 15-147-00525-00-00

To: 030908
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
NE NE NE
NE NE, SEC. 31, T 5 S, R 20 W

TECHNICIAN'S PLUGGING REPORT

330-4950 feet from S section line
330 feet from E section line

Operator License # 5447
Operator: Cities Service Oil and Gas Corp
Name & Address 3545 N.W. 58 Street
Oklahoma City, Ok. 73112

Lease Name Pinkerton Well # A 13
County Phillips 118.37
Well Total Depth 3642 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 211

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____
Address Hays, Kansas

Company to plug at: Hour: AM Day: 18 Month: June Year: 19 87

Plugging proposal received from E. G. Hutchinson

(company name) Cities Service (phone) _____

were: 8 5/8 set at 211' w/200 sks 5 1/2 set at 3638 w/150 sks. Open hole.
Perf. 4 SPF at 1760' Any 4 Spf. at 1125' Base Dakota and 50'.
Order 250 sks. Econolite 65/35 Poz 10% Gel 2% Dicol 6 sks Hulls.
Halliburton Gmt. Co. OWS water trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 AM Day: 18 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Squeeze down 5 1/2 csg 145 sks cmt. blend w/4 sks Hulls.

Max Psi. 500# Close in Psi 250#.
Squeeze down 8 5/8" - 5 1/2" annulus w/29 sks cmt. blend w/2 sks Hulls. Max. Psi. 500#
Close in 200# . Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-10-87
JUL 10 1987

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-10-87

INV. NO. 17465

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow