

11-18

4-041850

13-147-00521-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 07-27-41

SW SE NE /4 SEC. 31 , 05 S, 20 W  
2970 feet from S section line  
990 feet from E section line

Operator license# 5447

Lease: Pinkerton A Well # 1

Operator: OXY USA, Inc.

County: Phillips 117.58

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3618 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4, Inch @ 156 feet  
w/135 sxs.cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# \_\_\_\_\_

Address: Hays, Kansas 67601

Company to plug at: Hour: 12:00 P.M. Day: 18 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3610' w/100 sxs.  
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 2:30 P.M., Day: 18, Month: November, Year: 1996

Actual plugging report: Worked tubing at 40,000 overweight for about an hour when tubing parted. POOH with 106 jts. 2 3/8" tubing and ESP cable. ESP stuck across LKC. Made the decision to P&A this well. Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Installed 2" riser to surface. Rigged up H.L.S. and perfed at 1155' and 1800' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3100'. (Top of fish at 3130'). Pumped 65 sxs MIDCON 2 with 2% C.C. and 200# Cottonseed hulls. Pulled 48 jts. to 1700'. Pumped 85 sxs cement and 200# hulls. Cement circulated to surface. POOH with tubing. Hooked up to 5 1/2" casing and pumped 55 sxs cement. Max. P.S.I. 500#. S.I.P. 250#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% C.C. and 100# hulls. Max. P.S.I. 300#. S.I.P. 200#. Total cement used 255 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING , CASING \_\_\_\_\_ Elevation: 2196 K.B.

INVOICED

did [ ] did not [ ] observe the plugging.

DATE JAN 13 1997

INV. NO. 47335

Dennis L. Hamel  
(agent)

Form CP-2/3

1-10-97