

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20472-00-00
Spot: NWNWSENV Sec/Twnshp/Rge: 9-1S-34W
1480 feet from N Section Line, 1500 feet from W Section Line
Lease Name: CAHOJ UNIT Well #: 911
County: RAWLINS Total Vertical Depth: 4314 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

PROD Size: 5.5 feet: 4292 w/250 sxs cmt
SURF Size: 8.625 feet: 295 w/190 sxs cmt

\$140²¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2004 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 350 sxs Midcon II cement and 1000# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2004 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 295' w/190 sxs cement.
5 1/2" production casing set at 4292' w/250 sxs cement.
PBTD 4175'. DV tool set at 2965' w/400 sxs cement.
Cement did not circulate. Top of cement at 1858'. Junk in hole at 3040'.
Ran tubing to 2584' - pumped 85 sxs cement with 500# hulls.
Pulled tubing to 1291' - pumped 75 sxs cement with 500# hulls.
Cement to surface - pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 10 sxs cement.
Max. P.S.I. 300#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 20 sxs cement.
Max. P.S.I. 150#. S.I.P. 150#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4161 | 4163 | | |
| 4143 | 4149 | | |
| 4065 | 4068 | | |
| 4041 | 4044 | | |
| 4003 | 4009 | | |

RECEIVED
NOV 22 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #7330.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED
DATE 11-22-04
INV NO. 2005060842

NOV 10 2004

REPLACEMENT CARD

GETTY OIL COMPANY
 2705 VINE, UNIT 4
 HAYS, KS 67601

9-1-34W
 1480' FNL &
 1500' FWL, NW/4


#911 CAHOJ UNIT

CONTR MURFIN DRILLING COMPANY CTY RAWLINS

GEOL _____ FIELD CAHOJ

ELV 3116 KB SPD 5/9/83 CARD ISSUED 7/28/83 IP P 33 BO & 232 BWPD
 3111 GL LKC 4003-4163 OA

API 15-153-20,472



| SMP | Top | Depth/Datum |
|-------|-------|-------------|
| SC | | 2949+ 167 |
| OREAD | | 3887- 771 |
| LKC | | 3983- 867 |
| PBTD | | 4175-1059 |
| RTD | | 4314-1198 |

8 5/8 " 295/190SX; 5 1/2 " 4292/650SX
 NO DSTS
 CORE (1) 3982-4027 (LANS) - DETAILS NA
 CORE (2) 4027-4087 (LANS) - DETAILS NA
 CORE (3) 4087-4147 (LANS) - DETAILS NA
 CORE (4) 4147-4207 (LANS) - DETAILS NA
 CORE (5) 4207-4244 (LANS) - DETAILS NA
 MICT - CO, PF (LKC) 4194-97, W/4 SPF, AC 1000 G, SWB LD,
 NS, PF (LKC) 4184-92, W/4 SPF, SWB DWN, NS, PF (LKC) 4161-
 63, W/4 SPF, AC 500 G, SWB LD, SO, PF (LKC) 4143-49, W/4
 SPF, AC 2300 G, SWB LD, SO, PF (LKC) 4065-68, W/4 SPF, AC
 1000 G, SWB LD, SO, PF (LKC) 4041-44, W/4 SPF, AC 1000 G,
 SWB LD, SO, PF (LKC) 4003-09, W/4 SPF, AC 1000 G, SWB LD,
 SO, SET 2 3/8 " TBG AT 4172, R & T, PLUGGED OFF PFS 4184-
 97 OA, POP, P 104 BO & 612 BWPD (GR 35.9%), 10/21/83

**CORRECTION & INFO RELEASED: 1/19/84 - ADDED COMP INFO;
 CORRECTED PROD INTV - WAS 4161-63**