

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00485-00-00
Spot: CNEÑWSE Sec/Twnshp/Rge: 28-5S-20W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: REESE E Well Number: 10
County: PHILLIPS Total Vertical Depth: 3625 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 195 250 SX CMT
Production: Size 5.5 feet: 3625 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/09/2002 3:00 PM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: RIC HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2701

Proposed Plugging Method: Ordered 300 sxs of Mid-Con II cement and 900# hulls.
Perforate 1710' and 1050'.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/09/2002 5:45 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" Surface casing set at 195' w/250 sxs cement.
5 1/2" Production casing set at 3625' w/150 sxs cement.
Perforated 5 1/2" casing at 1710' and 1050'.
Ran 2" tubing to 3579' - pumped 100 sxs cement with 300# hulls.
Pulled 2" tubing to 1754' - pumped 100 sxs cement with 200# hulls.
Circulated cement to surface.
Pulled 2" tubing surface.
Topped 5 1/2" production casing with 20 sxs cement.
S.I.P. 300#.
Connected to 8 5/8" surface casing - pumped 80 sxs cement with 200# hulls.
Max. P.S.I. 450#. S.I.P. 100#.
Plug complete.

RECEIVED
DEC 13 2002
KCC WICHITA

Remarks: SWIFT CEMENT COMPANY.

Plugged through: TBG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

DEC 10 2002

INVOICED
DATE 12-13-02
INV. NO. 2003060948

Form CP-2/3

CITIES SERVICE

#10

REESE E

Arb 28-5-20W
NE NW SE

PHILLIPS County

Contr.

E 2180 Comm. 1-19-49 Comp. 2-25-49 IP 1727 BOPD

Tops	Depth	Datum
HEEB	3281	-1101
LANS	3317	-1137
B/KC	3524	-1344
ARB	3569	-1389
BASAL SD	3617	-1437
T.D.	3625	-1445

Casing

8" 195 PERF 3567-90
 5" 3625 PERF 3581½-90
 PERF 3576-81½
 PERF 3567-73
 2700' OIH/16 HRS
 FMP 224 BO/15 HRS
 ACID 1500

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

KCC

DEC 12 2002

HAYS, KS

41010 Y/M

2310

607 1/4