

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 19 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bankoff Oil Company 15-147-00857-0000

Complete Address 1119 Sherman Great Bend, Kansas 67530

Lease Name Bowman A Well No. 3

Location SE NW SE Sec. 3 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3381'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 9:30 A Day 18 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3381' 10 3/4 csg set at 171' cwc 125 sk. Cmt. Mat. 50-50 poz 6% gel.

5 1/2 csg set at 3371 cw 250 sk cmt.

4 1/2 liner set from (0-1500)

Filled 5 1/2 csg W/sd (3350-3381) Dumped 5 sk cmt W/dump bailer. (3315-3350)

Recovered 499' of 4 1/2 csg & 467' of 5 1/2 csg.

Pumped down 10 3/4 csg with 20 sk gel W/500 lbs hulls, --70 sk cmt --8 sk gel & water--
--released 10 3/4 plug and pumped 70 sk cmt. PP 500 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 4-19-72

INV. NO. 5593