

KANSAS

4

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20136-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Abercrombie Drilling, Inc. 9-20-71

Complete Address 801 Union Center Wichita, Kansas

Lease Name _____ States _____ Well No. 1

Location SE SW NW Sec. 3 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3417'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX

Other well as hereafter indicated _____

Plugging Contractor Co. Teels

Address _____ License No. _____

Operation Completed: Hour 9:30 P Day 16 Month 9 Year 1971

The above well was plugged as follows:

RTD 3417' 8 5/8 csg set at 223' owe Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo P. Massey
Well Plugging Supervisor

INVOICED

DATE 9-22-71

INV. NO. 4362-W