

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1975
10-17-75
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Bankoff Oil Company 15-147-00573-0000

Complete Address P. O. Box 5, Pawnee Rock, Kansas 67567

Lease Name Brown Well No. 3

Location SE NE SE Sec. 3 Twp. 55 Rge. (E) (W) 20

County Phillips Total Depth 3285'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor SW Casing Pulling Co.

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:45 P Day 15 Month 10 Year 1975

The above well was plugged as follows:

Total Depth 3285' 80 3/4 csg set 217' cwc 200 sk.

5 1/2 csg set 3283' cw 125 sk cem.

5 1/2 csg PFS (3190-3254)

Filled 5 1/2 csg W/sd (3285-3175) dumped 4 sk cem W/dump bailer. (3175-3140)

Cutoff & recovered 2200' of 5 1/2 csg.

Pumped down 10 3/4 csg with 20 sk gel & water W/500 lbs hulls -70 sk 50-50 poz 6%-

15 sk gel & water -released 10 3/4 plug & pumped 70 sk 50-50 poz 6%. PP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 10/20/75

INV. NO. 2083-W