

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1977
6-28-77
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 147- 00572-0000 (of this well)

Operator's Full Name Bankoff Oil Company

Complete Address P. O. Drawer 2479, Tulsa, Oklahoma 74101

Lease Name Brown Well No. 2

Location NE SW SW ^{RCSR} SWSWNE Sec. 3 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3385'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 24 Month 6 Year 1977

The above well was plugged as follows:

Total Depth 3385' 10 3/4 csg set 180' cwc 100 sk.

5 1/2 csg set 3384' cw 100 sk cem.

5 1/2 csg PBSD 3200' with Perf. (3136'-3144')

Top of tbg fish 1290'.

Set 5 1/2 wood plug at 1290' -poured 10' sd -dumped 4 sk cem W/dump bailer.

Cutoff & recovered 718' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 10 3/4 csg with 20 sk gel W/300 lbs hulls.

75 sk 50-50 poz 6% -displaced with 10 sk gel & water & capped with 75 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 6-28-77

INV. NO. 5402-W