

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 138-11 County: Phillips 15-147-19006-0000

Location: CE¹/₂ SW SE Sec. 3 Twp. 5 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3458

I have this date completed supervision of plugging of:

Lease Name: Bowman Well No. 4

Operator's Full Name: White Eagle Oil Co

Complete Address: Box 255 Garden City, Kans

Plugging Contractor: Ace Pipe Pulling Co & Globe Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 12 Noon Day 29 Month 11 Year 58

The above well was plugged as follows:

10 3/4" 168' circulated with cement - 7" 3450' with 175 sax cement behind,
perforated at 3198'.

Filled with sand to 3100', set 6 sax cement with dump bailer, pulled 1339'
7" to 600', circulated hole with heavy mud (Gel) through 7" at 600',
displaced 50 sax cement through 7" at 600', heavy mud to 140', displaced
20 sax cement through 7" at 140', heavy mud to 35', set rock and 10 sax
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 - 1958 12-9-58

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 3 T S R 20W
BOOK PAGE 132 LINE 11