

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 138-10 County: Phillips 15-147-00856-0000

Location: SE NE SW Sec. 3 Twp. 5 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3420

I have this date completed supervision of plugging of:

Lease Name: Bowman Well No. 2

Operator's Full Name: White Eagle Oil Co

Complete Address: Box 255 Garden City, Kans

Plugging Contractor: Ace Pipe Pulling Co & ~~Est~~ Globe Cementing Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 2 Month 12 Year 58

The above well was plugged as follows:

10 3/4" 157' circulated with cement - 7" at 3406" with 250 sax cement
behind - 20' 5 1/2" liner.

Filled with sand to 3390', set 4 sax cement with dump bailer, pulled 1400'
7" to 600', circulated hole with heavy mud (gel) through 7" at 600',
displaced 20 sax cement through 7" at 600', heavy mud to 140', displaced
20 sax cement through 7" at 140', heavy mud to 30', set rock and 10 sax
cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: *Jedon Petty*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

PLUGGING
FILE SEC 3 T 5 R 20 W
BOOK PAGE 132 LINE 10

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 - 1958
CONSERVATION DIVISION
Wichita, Kansas