

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bankoff Oil Company 15-147-00047-0000

Complete Address Box 2479 Tulsa, Oklahoma 74101

Lease Name Bowman "A" Well No. 1

Location NW NW SE Sec. 3 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3555'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1 P Day 24 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3555' 10 3/4 csg set at 158' cwc 100 sk.

5 1/2 csg set at 3552' cw 200 sk cem.

5 1/2 csg PBD 3398' & perf. (3194-3197)

Filled 5 1/2 csg W/sd (3398-3150) dumped 5 sk cmt W/dump bailer. (3150-3115)

Recovered 1010' of 5 1/2 csg.

Pumped down 10 3/4 csg with 25 sk gel & water W/500 lbs hulls -70 sk cmt -10 sk gel & water -released 10 3/4 plug & pumped 80 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/27/74

INV. NO. 9764-W

Signed: Rio J. Massey
Well Plugging Supervisor