

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00125-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 4 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
5-4-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leland R. Baird

Complete Address Logan, Kansas

Lease Name Hockett Well No. 1

Location SE NE NE Sec. 3 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3391

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1P Day 2 Month 5 Year 1970

The above well was plugged as follows:

Total Depth 3391' 8 5/8 csg set at 201' cwc 120 sk.

5 1/2 csg set at 3363' cw 100 sk cmt.

5 1/2 csg perf. (3122-3126)

Filled 5 1/2 csg W/sd (3350-3391) Dumped 5 sk cmt W/dump bailer. (3310-3350)

Set wood plug at 3100 Poured sd (3090-3100) Dumped 5 sk cmt W/dump bailer. (3050-3090)

Cutoff and recovered 2520' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, 70 sk poz 6%, 10 sk

gel, plug and 50 sk poz 6%. Max. pres. 250 lbs. SI pres 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 5/4/70

INV. NO. 1829-4