

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bankoff Oil Company 15-147-00571-0000

Complete Address: P.O. Drawer 2479 Tulsa, Oklahoma

Lease Name Brown Well No. 1

Location NW NE SE Sec. 3 Twp. 5 Rge. 20 (E) (W) X

County Phillips Total Depth 3410

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 1P Day 28 Month 8 Year 1968

The Above well was plugged as follows:

Total Depth 3410' 10 3/4 csg set at 157' cwc.

7" csg set at 3374' cw 150 sc cement.

7" PBTD 3120' with top perf at 3092'

Filled 7" csg with sand to 3080' and dumped 6 sc cement with dump bailer.

Cutoff and recov. 1080' of 7" csg.

Pumped thru 10 3/4 swage with 30 sc gel & water W/6 sc hulls, 1 sc hulls and 150 sc

50-50 poz cement W/6% total gel. Bapped with 100 lbs. hulls and 3 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mussey
Well Plugging Supervisor

DATE 9/3/68
INV. NO. 8381-4