

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00457-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

8-20-70

Operator's Full Name Bankoff Oil Company,

Complete Address Drawer #2479, Tulsa, Oklahoma.

Lease Name Perry Well No. 2

Location SE-SE-SE Sec. 3 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3415'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated.

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 3:30 PM Day 17 Month 8 Year 1970

The above well was plugged as follows:

191'--810 3/4" Surface casing, cement circulated.  
3411'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3189'. Top perforations from 3160' to 3166'. ~~XXXXXX~~

Sanded well back to 3150' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 130 Sx. cement from 775' to 475' then 9 sacks gel from 475' to 200' and followed with 35 Sx. cement from 200' to 130' then 10 Sacks gel from 130' to 30' and finally 15 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in pressure--50#. (Mudding and cementing operations by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 8/20/70

INV. NO. 2414-W