

15-147-00011-00-01

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Company
Complete Address: Box 553 Russell, Kansas 67665
Lease Name Wiltrout Well No. 1
Location C S/2 SE NE Sec. 18 Twp. 5 Rge. 20 (E) (W) XX
County Phillips Total Depth 3736
Abandoned Oil Well Gas Well Input Well SWD Well XX D & A
Other well as hereafter indicated:
Plugging Contractor: Co. Tools
Address: License No.
Operation Completed: Hour 12N Day 25 Month 10 Year 1968

The Above well was plugged as follows:

Total Depth 3736' 8 5/8 csg set at 170' cwc.
5 1/2 csg set at 3672' cw 200 sc cmt. 5 1/2 csg DV tool set at 1660' cwc
PBTD at 3405 and squeezed with 50 sc cmt. Top of cmt 2731
Run tubing to 2730 and displace 25 sc cmt (2530-2730)
Pulled tubing to 1670 and circ gel to surface. Displaced 15 sc cmt. (1550-1670)
Pulled tubing to 900' and displaced 15 sc cmt. (780-900)
Pulled tubing to 180' and circ. 25 sc cmt to surface.
Pulled tubing to surface. Cutoff 5 1/2 & 8 5/8 csg and capped with 2 sc cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Bo Z. Mueser
Well Plugging Supervisor

INVOICED
DATE 10/28/68
INV. NO. 8720-4