

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20071-00-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1972

CONSERVATION DIVISION
Wichita, Kansas

10-25-72

Operator's Full Name Leland Baird,

Complete Address Logan, Kansas.

Lease Name States Well No. 1

Location SE-NE-NW Sec. 18 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3520'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30 PM Day 23 Month 10 Year 1972

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 135 Sx.
3519'--4 1/2" Production casing cemented on bottom with 200 Sx. Top of cement @ 2440'.
Well plugged back to 3288'. Top perforations from 3262' to 3264'.

Sanded well back to 3250' and set 5 Sx. cement with dump bailer. Pulled 4 1/2" casing
(2310') and squeezed well initially with 3 sacks hulls, 20 sacks gel and 2 sacks hulls
and followed with 110 Cu. Ft. cement then 10 sacks gel and finally 75 Sx. cement.

Maximum pump-in pressure-900#. Final shut-in pressure-350#. (Mudding and cementing
operations by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 10/27/72
INV. NO. 6523-4