

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00503-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

1-26-73

Operator's Full Name Cities Service Oil Company

Complete Address 710 Sutton Place Wichita, Kansas 67202

Lease Name Reese "D" Well No. 2

Location SW SE NE Sec. 29 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3688'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 12:00 Day 24 Month 1 Year 1973

The above well was plugged as follows:

Total depth 3688' 8 5/8 csg set at 158' cwc 125 sk.

5 1/2 csg set at 3688' cw 100 sk cmt.

5 1/2 csg perf. (3601)

Set castiron plug at 3585' -Dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 612' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls, -released 8 5/8 plug and pumped 120 sk cmt by "HOWCO", PP 250 lbs SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1/30/73

INV. NO. 6911-W