

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-00504-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1970
CONSERVATION DIVISION
Wichita, Kansas
9-17-70

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Reese "D" Well No. 3

Location G SW NW NE Sec. 29 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3632'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11 A Day 16 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3632' 8 5/8 csg set at 199' cwc 250 sk.

5 1/2 csg set at 3631' cw 150 sk cmt.

5 1/2 csg PBTD 3611' with top perf. (3368-3372)

Filled 5 1/2 csg W/sd (3350-3611) Dumped 5 sk cmt W/dump bailer. (3310-3350)

Recovered 685' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 15 sk gel W/3 sk hulls, -70 sk poz 6%, -

10 sk gel, -plug and 50 sk poz 6%.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Messing
Well Plugging Supervisor

DATE 9-17-70

INV. NO. 2547-W