

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-147-00142-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1961 7-18-61

CONSERVATION DIVISION
Wichita, Kansas

File No. _____ County: Phillips

Location: SW NW NE Sec. 18-5-20 Rge. _____ (E) _____ (W) 20

Name of Field: _____ Total Depth: 3455

I have this date completed supervision of plugging of:

Lease Name: States Well No. 1

Operator's Full Name: R. W. Shields

Complete Address: 308 Rule Bldg Wichita, Kansas

Plugging Contractor Central Pipe Pulling

Address: Great Bend, Kans License No. 459

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 13 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 208' circulated with cement - 5 1/2" 3455' with 125 sax cement -

PB to 3410', perforated 3229'

Set plug at 3200', 50' sand & 5 sax cement - pulled 2671' 5 1/2" to

550', circulated hole with heavy mud through 5 1/2" (39 sax Gel), displaced

20 sax cement through 5 1/2" at 550', heavy mud to 180', displaced 20 sax

cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax cement

to bottom cellar.

Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 7/20/61

INV. NO. 3404-W