

KANSAS

Form CP-3
Rev. 6-4-68



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-00502-06-00

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 26 1973
CONSERVATION DIVISION
Wichita, Kansas
1-26-73

Operator's Full Name Cities Service Oil Company
Complete Address 710 Sutton Place Wichita, Kansas 67202
Lease Name Reese "D" Well No. 1
Location SW SW NE Sec. 29 Twp. 5 Rge. (E) (W) 20
County Phillips Total Depth 3727'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co., Inc.
Address Box 405 Chase, Kansas 67524 License No. 436
Operation Completed: Hour 10:45 A Day 24 Month 1 Year 1973

The above well was plugged as follows:

Total Depth 3727' 8 5/8 csg set at 162' cwc 125 sk.
5 1/2 csg set at 3727' cw 150 sk cmt.
5 1/2 csg PBTB 3661' with top perf. (3648')
Filled 5 1/2 csg W/sd (3625-3661) Dumped 5 sk cmt W/dump bailer.
Cutoff and recovered 506' of 5 1/2 csg.
Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls, -released 8 5/8 plug
and pumped 120 sk cmt by "HOWCO". PP 300 lbs SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. M. Casey
Well Plugging Supervisor

INVOICED

DATE 1/30/73
INV. NO. 6910-W