


15-147-00713-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Phillips County. Sec. 28 Twp. 5 Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines NE SW NW
Lease Owner Cities Service Oil Co.
Lease Name Vehige B Well No. 4
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 6/23/55 19
Application for plugging filed 6/27/55 19
Application for plugging approved 6/29/55 19
Plugging commenced 6/24/55 19
Plugging completed 6/25/55 19
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>granite</u>				<u>8-5/8"</u>	<u>202'</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 190', set plug, 1/2 sx hulls and 15 sx. cement. Mud to 40'
1/2 sx. hulls and 10 sx cement to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drlg. Co.
Address Tulsa, Oklahoma

STATE OF KANSAS, COUNTY OF BARTON, ss.
R. L. Higginbottom (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 553, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1955
[Signature] Notary Public.

My commission expires March 17, 1959

PLUGGING
FILE SEC 28 T 5 R 20W
BOOK PAGE 130 LINE 28

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1955
CONSERVATION DIVISION
Kansas
7-12-55

15-147-00713-00-00

WELL RECORD

Company Cities Service Oil Co. Well No. 4 Farm Yehigo #37
 Location 990' North and 990' East of 1/4 Cor. Sec. 28 T. 5 R. 20W
 Elevation 2205 (2200 Gr.) County Phillips State Kansas
 Drlg. Comm. June 19, 1955 Contractor Harbour Drilling Company
 Drlg. Comp. June 23, 1955 Acid None
 T. D. 3710' Initial Prod. Dry Hole - P. & A. 6-24-55

CASING RECORD:

3-5/8" @ 202' ann. 200 wt cement

FORMATION RECORD:

clay	6-50
clay & sand	170
shale	690
shale & shells	1230
sand	1430
shale	1725
anhydrite	1755
shale & shells	1965
shale & lime	2700
lime	2825
shale & lime	3120
lime	3208
shale & lime	3315
lime & shale	3368
lime	3560
lime & shale	3624
coars sand & shale	3629
coars sand	3632
sand	3690
sand & granite wash	3710 T. D.


Neckline	3525'
Edge	3555'
Landing	3574'
German Sand	3626'
Keegan	3628'
Granite Wash	3705'
Penetration	5'
Total Depth	3710'

D. S. T. 3627-35, open 30 mins., recovered 6' mud; B. H. P. 970#/30 mins.

D. S. T. 3632-40, open 30 mins., recovered 2' mud; B. H. P. 750#/30 mins.

D. S. T. 3635-45, open 1 hr., recovered 720' salt water; B. H. P. 945#/30 mins.

D. S. T. 3630-3710, open 1 hr., recovered 2250' water; B. H. P. 1040#/30 mins.



7-7/8" rotary hole.

PLUGGING
 PAGE SEC 28 T 5 R 20W
 BOOK PAGE 130 LINE 28

RECEIVED
 STATE GEOLOGICAL SURVEY
 CONSERVATION DIVISION
 7-12-55

