

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Elder & Vaughn, Inc.
Address: PO Box 18938 OKC OK 73154
Phone: (405) 842 8877 Operator License #: 7457

API Number: 15-175-21784-00-00
Lease Name: Jaquart
Well Number: 1-30

Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): 150 - South C - W/2
2490 Feet from North / South Section Line

The plugging proposal was approved on: 10-29-04 (Date)
by: Richard Lacy (KCC District Agent's Name)

3960 Feet from East / West Section Line

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Sec. 30 Twp. 33 S. R. 32 East West

Producing Formation(s): List All (If needed attach another sheet)

County: Seward 1-16-2000 KCC

Herington Depth to Top: 2610 Bottom: 2622 T.D. _____

Date Well Completed: 12-18-99 BEM

Upper Kreider Depth to Top: 2634 Bottom: 2644 T.D. 2770

Plugging Commenced: 10-29-04 RBDMS

Depth to Top: _____ Bottom: _____ T.D. 2779 RBDMS

Plugging Completed: 11-1-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>Herington</u>	<u>Gas & wtr.</u>	<u>2610</u>	<u>2622</u>	<u>8 5/8</u>	<u>598</u>	<u>-</u>
<u>Upper Kreider</u>	<u>-</u>	<u>2634</u>	<u>2644</u>	<u>4 1/2</u>	<u>2776</u>	<u>961</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rods & tubing stuck in hole. Top of junk @ 1000. Shot 4 1/2 @ 961. Mixed 300 lb. hulls & mud to circ. hole. Mixed 50 sx plug from 961 to 811. Woc Tag top of plug @ 906. 50 sx 630 to 480 10 sx 40 to 0 Cut & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151

Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Elder & Vaughn Inc.

State of Oklahoma County, Oklahoma, ss.

Jack H. Vaughn (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) _____

(Address) PO Box 18938 OKla. C.F., Ok. 73154

SUBSCRIBED and SWORN TO before me this 17 day of November, 20 04

Barbara Brothers
Notary Public

My Commission Expires: December 31, 2005

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 19 2004
KCC WICHITA

B