

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Comanche Resources Company

Address: 6520 N. Western Ave., Suite 300

Phone: (405) 755-5900 Operator License #: 32384

Type of Well: Gas Docket #: (If SWD or ENHR)

The plugging proposal was approved on: 10/07/04 7.29.04 KCC BEM 11/22/04 RBDMs by: Steve (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet) Pawnee Depth to Top: 5034' Bottom: 5052' T.D. 6250'

API Number: 15-033-20858-00-01

Lease Name: Bird

Well Number: 2-10

Spot Location (QQQQ): - - SW - SW

660' Feet from North / South Section Line

660' Feet from East / West Section Line

Sec. 10 Twp. 32 S. R. 19 East West

County: Comanche

Date Well Completed: 9/16/92 3-1-1999 11/22/04

Plugging Commenced: 11/02/04

Plugging Completed: 11/03/04

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten data for casing sizes and depths.

RECEIVED NOV 22 2004 KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

T.O.O.H. w/155 jts 2 7/8" 6.4# J55 R.U. down hole wireline specialist. T.I.H. and set C.I.B.P. @ 4610' w/ 2 sks cmt. Loaded hole w/ 40 bbls 2% KCL, Removed wellhead. Installed pole & preformed stretch test. Free pipe @ 4210', T.I.H. chemical cutter. 1st cut @ 4354', 2nd cut @ 4250', worked pipe free. Shut down for day. T.O.O.H. w/ csg laying down 50 sks plug 1058', so sks plug 650', 20 sks @ surface, cmt pk class H, 60-40+ 6%gel. Recovered 100 jts 5 1/2" 15.5# J55 csg 4250', finished plugging operations, R.U. clean location and move on.

Name of Plugging Contractor: North Star Well Service License #: 2140379 33115

Address: P.O. Box 1749 Woodward, OK 73802

Name of Party Responsible for Plugging Fees: Comanche Resources Company

State of Oklahoma County, Oklahoma, ss.

Dawn Smith (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Dawn Smith

(Address) 6520 N. Western Ave., Suite 300 Oklahoma City, OK 73116

SUBSCRIBED and SWORN TO before me this 17th day of November, 20 04

Laura Gilbert Notary Public My Commission Expires: Expires 11/06/07 Comm. No. 99016806

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature/initials