

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21358-00-01

LEASE NAME Pauly

RECEIVED

NOV 22 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2230 Ft. from S Section Line

3640 Ft. from E Section Line

SEC. 13 TWP. 28S RGE. 19 ~~XXX~~ (W)

COUNTY Kiowa

Date Well Completed 10/1/94

Plugging Commenced 11/4/04

Plugging Completed 11/9/04

LEASE OPERATOR TGT Petroleum Corporation

ADDRESS 7570 W. 21st-Bldg.1010-D, Wichita, Ks. 67205

PHONE#(316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (verbal approval - not on location) (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top _____ Bottom _____ T.D. 4910'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	498'	None
				5 1/2"	4898'	2509'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Set five sacks cement on top of sand plug @ 3800'. Pump 12 sacks gel set. Plug @ 1250' with 50 sacks cement and 100# bulls; set plug at 510' with 50 sacks cement and 100# bulls; plug at 40'/w/10 sacks cement. All cement 60/40 Posmix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) B. Lynn Herrington, Ex. W-P
7570 W.21st-Bldg.1010-D,Wichita, Ks.



Subscribed and sworn to before me this 16th day of November, 2004

Judith K. Moser
Judith K. Moser Notary Public

My Commission Expires: 5/17/05