

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-20,648-00-00  
LEASE NAME Becker-Rice  
WELL NUMBER 2  
4620 Ft. from S Section Line  
3300 Ft. from E Section Line  
SEC. 13 TWP. 28S RGE. 19 (E) (W)  
COUNTY Kiowa  
Date Well Completed 10/25/80  
Plugging Commenced 11/8/04  
Plugging Completed 11/10/04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR TGT Petroleum Corporation

ADDRESS 7570 W. 21st-Bldg.1010-D, Wichita, Ks. 67205

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-i filed? NA If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4825'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	368'	None
				5 1/2"	4824'	2403'

RECEIVED  
NOV 22 2004  
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Set five sack plug on sand plug @ 4821'. Pump 12 sack gel set plug @ 1250'/w/50 sacks cement/w/100# hulls; set plug @ 390' with 50 sacks cement/w/100# hulls @ 40'/w/10 sacks to top of pipe. All cement 60/40 Posmix  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mikes Testings & Salvage License No. 31529  
Address 7579 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205 PO Box 467 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.  
STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington  
B. Lynn Herrington-Ex. V-1  
(Address) 7570 W. 21st-Bldg.101-D, Wichita, Ks.



Subscribed and sworn to before me this 16th day of November, 2004  
Judith K. Moser  
Judith K. Moser Notary Public  
My Commission Expires: 5/17/05

RECEIVED

NOV 3 1980

CONTRACTOR'S WELL LOG

OPERATOR:	TGT Petroleum Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BECKER RICE #2
LOCATION:	C NE NW, Section 13-28S-19W Kiowa County, Kansas
SPUD DATE:	10-11-80
COMPLETION DATE:	10-25-80

0	374	Sand & Shale
374	1159	Redbed & Shale
1159	1171	Anhydrite
1171	1541	Redbed & Shale
1541	4825	Lime & Shale
	4825	Rotary Total Depth

Spud hole @ 7:00 p.m. 10-11-80. Drilled 374' of a 12-1/4" hole. Ran 8 joints of 8-5/8" 24# used casing (tally 358.66' overall) Set @ 368.58'. Cemented with 350 sx. of common, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 10:45 p.m. 10-11-80.

T.D. 4825'. Ran 118 joints of 5-1/2" casing (tally 4830') Set @ 4825'. Cemented with 250 sx. Job complete @ 9:25 p.m. 10-25-80.

SAMPLE TOPS:

Anhydrite	1159'
B/Anhydrite	1171'

STATE OF KANSAS        )  
                              ) SS  
COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the BECKER RICE #2, C NE NW, Section 13-28S-19W, Kiowa County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
Jack L. Partridge, Asst. Sec.-Trea

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 30th day of October, 1980.

Jeanette A. Metheny  
Jeanette A. Metheny, Notary Public

