

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

Well was completed on:  
API NUMBER 8/20/42

#4  
15-147-00490-00-00

LEASE NAME Vehicle A

WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 28 TWP. 5S RGE. 20 (E) or (W)

COUNTY Phillips

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2309 OPERATORS LICENSE NO. 5447

Date Well Completed 8/20/42

Character of Well Oil

Plugging Commenced 5/24/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/27/93

The plugging proposal was approved on March 9, 1993 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3533 Bottom 3542 T.D. 3614

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To   | Size   | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| Arbuckle  | Oil     | 3533 | 3542 | 8 5/8" | 1661   |            |
|           |         |      |      | 5 1/2" | 3614   |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Perf @ 1100' w/4 shot/ft & 1770 w/4 shots/ft. Ran 115 lbs - 2 7/8 Tbg. to 3508' Pumped  
7 BBL Gel 25sx 60/40 Poz w/100# hulls. Pulled 2 7/8 Tbg. to 1778' Pumped 110sx w/200#  
hulls - cmt circ. to surface. Press 5 1/2 Csg w/50sx 100# hulls tied onto 8 5/8 Csg. pumped  
(If additional description is necessary, use BACK of this form.) 50sx w/100# hulls

Name of Plugging Contractor J. W. Gibson Well Service License No. 5866

Address 505 W. Commercial, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

GREG ROWE

(Employee of Operator) or (Operator) o

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts  
statements, and matters herein contained and the log of the above-described well as filed th  
the same are true and correct, so help me God.

(Signature) Gregory C. Rowe RECEIVED  
STATE CORPORATION COMMISSION

(Address) P. O. Box 26100, OKC, OK 73126-0100 JUN 16 1993

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 93

Jimmy L. Braila  
Notary Public  
Wichita, Kansas

My Commission Expires: 8/21/96

6-16-93