

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15147-00489-00-00

Well was completed on:

API NUMBER 6-18-42

LEASE NAME Vehige A

WELL NUMBER 3

1650 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 28 TWP. 5S RGE. 20 (W)

COUNTY Phillips

Date Well Completed 6-18-42

Plugging Commenced 6-6-1989

Plugging Completed 6-6-1989

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 15, 1989 (date)

by Mr. Dale Balthazor (KCC District Agent's Name).

Well was completed on:
 Is ACO-1 filed? 6-18-42 If not, is well log attached? yes

Producing Formation Reagan Depth to Top 3596' Bottom 3598' T.D. 3665'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Reagan	Oil	3596	3598	8-5/8"	165'	0
				5-1/2"	3665'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perf. the Stone Corral at 1730' & below the Dakota at 1090' w/3 SPE. Tied onto the prod. csq. and filled the 5-1/2" to surf. w/300 sx 65/35 poz. w/8% + 250# hulls. Tied onto the 8-5/8" csq. & filled the annulus to surf. w/150 sx. cmt. + 2 sx Flo. & 250# hulls. State witness: Mr. Dale Balthazor (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Service Company LICENSE NO.

Address Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss. Wichita, Kansas

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 89

Marsha G. Wilson
 Notary Public

My Commission Expires: 4-1-92

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 12 1989
 CONSERVATION DIVISION
 Wichita, Kansas 6-12-89