

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 100 Colorado Derby Bldg
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

18-147-00487-00-00

API NUMBER 15-NA

LEASE NAME Vehicle A

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to
 Cons. Div. Office within
 30 days.

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 28 TWP. 5S RGE. 20 (x) or (W)

COUNTY Phillips

Date Well Completed 6/25/41

Plugging Commenced 8/31/94

Plugging Completed 8/31/94

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/20/94 (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Reagan Depth to Top 3568 Bottom 3654 T.D. 3654

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
Formation	Content	From	To	Size	Put in	Pulled Out
<u>Reagan</u>	<u>Oil</u>	<u>3568</u>	<u>3654</u>	<u>8 5/8</u>	<u>166</u>	
				<u>5 1/2</u>	<u>3654</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Perf'd @ 1725 & 1090. RIH w / 2 3/8 tbq to 3400. Mixed & pumped 60sks 60/40 Poz w/10% gel, 1/4# sk Flocele w/150# hulls. Pulled tbq to 2200. Mixed & pumped 75sks cmt w/200# hulls. Pulled tbq to 1050. Mixed & pumped 60sks, circ'd cmt to surf. POOH w/ tbq. Hooked up to 8 5/8. Mixed & pumped 50sks w/100# hulls. 150# shut-in press. Hooked up to 5 1/2. (See back of form)
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service High Plains License No. 5866 8003

Address 505 W Commercial, Logan, KS 67646 P.O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
 STATE CORPORATION (Signature)

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 12th day of September, 19 94

CONSERVATION DIVISION
 WICHITA, KANSAS

Kay Ann Kilmer
 Notary Public

My Commission Expires: 5-2-98