

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-147  
LEASE NAME REESE E

00485-0000  
RSP/KCC  
JAN 06 2003  
01-06-03  
KCC WICHITA

WELL NUMBER 10  
NOTICE: Fill out **completely** 2310 Ft. from S Section Line  
and return to Cons. Div. 1650 Ft. from E Section Line  
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc. SEC 28 TWP. 5S RGE. 20W (E) or (W)  
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202 COUNTY PHILLIPS  
PHONE # (316 ) 267-3241 OPERATORS LICENSE NO. 30606 Date Well Completed 1/27/49  
Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 12/10/02  
Plugging Completed 12/10/02

The plugging proposal was approved on 12/10/02 (date)  
By Witnessed and approved by Darrel Dipman w/KCC Hays,KS. (KCC District Agent's Name).  
Is ACO-1 filed? ? If not, is well log attached? no

Producing Formation GORHAM Depth to Top 3565 Bottom 3574 TD 3623 Show  
depth and thickness of all water oil and gas formations

OIL, GAS, OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	196	8 5/8	196	0
		production	3623	5 1/2"	3623	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Plugged well as follows: Perf well @ 1710' & 1050'. TIH w/ 2 3/8" tbg. to 3580'. Pumped 100 sxs multi density cmt w/400# hulls. Pulled tbg to 1750', pump 100 sxs cmt w/200#hulls. TOH w/ rest of tbg. Pumped 15 sxs cmt w/100# hulls. Held 100#. 290 xsx cmt & 700# hulls total. Well P/A. Witnessed and approved by Darrel Dipman w/KCC Hays , KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address  
250 N. Water, Suite 300; Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK ,SS.  
Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Tom W. Nichols  
(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of Jan. 2003

Notary Public - Barbara J. Dodson Barbara J. Dodson  
My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



QR



CHARGE TO: Murfin Drlg. Co.  
 ADDRESS:  
 CITY, STATE, ZIP CODE: Logan Ks

TICKET No 5112

PAGE 1 OF 1

SERVICE LOCATIONS 1. Hayp 16 WELL/PROJECT NO. E-10 LEASE Reese COUNTY/PARISH Phillips STATE KS CITY DATE 12-9-02 OWNER Jane

2. TICKET TYPE  SERVICE CONTRACTOR RIG NAME/NO. Murfin SHIPPED VIA 105 DELIVERED TO Logan ORDER NO.

3.  SALES WELL TYPE oil WELL CATEGORY Abandoned JOB PURPOSE P.T.A. WELL PERMIT NO. WELL LOCATION

4. REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT
		LOC	ACCT	DF							
575		1			MILEAGE 105	50		mi		2.50	125.00
576		1			Pump charge	1		SA			500.00
330					5mD Cement	300		SKS		9.50	2850.00
275					Hulls	9		SKJ		22.00	198.00
581					Bulk Service charge	300					300.00
583					Drayage	745	75		T.M.	75	559.31

RECEIVED  
 JAN 06 2003  
 KCC WICHTA

**LEGAL TERMS:** Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X  
 DATE SIGNED 12-9-02 TIME SIGNED 1:00  A.M.  P.M.

REMIT PAYMENT TO:  
 SWIFT SERVICES, INC.  
 P.O. BOX 466  
 NESS CITY, KS 67560  
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?				4532.31
WE UNDERSTOOD AND MET YOUR NEEDS?				
OUR SERVICE WAS PERFORMED WITHOUT DELAY?				
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				240.21
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND				TOTAL
				4772.52

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR Lenny APPROVAL R. Ackman

Thank You!

