

OF KANSAS
 CORPORATION COMMISSION
 Colorado Derby Bldg
 Wita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-147-60552-00-00

API NUMBER 15-NA

LEASE NAME Pearson B

WELL NUMBER 3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to
 Cons. Div. Office within
 30 days.

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 5S RGE. 20 (X) or (W)

COUNTY Phillips

Date Well Completed 12/21/46

Plugging Commenced 8/31/94

Plugging Completed 8/31/94

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/20/94 (date)

by Dennis Hamel (KCC District Agent's name)

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation LSG-KC Depth to Top 3280 Bottom 3486 T.D. 3578

Show depth and thickness of all water, oil and gas formations.
 OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
LSG-KC	Oil	3280	3486	8 5/8	197	
				5 1/2	3567	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Perf'd @ 1750 & 1115. RIH w/tbq to 2368. Mixed & pumped 85sx 60/40 Poz w/10% gel, 1/4#sk Flocele, 250# hvlls. Pulled tbq to 1185. Mix & pumped 75 sx 60/40 poz w/10% gel & 1/4# sk Flocele w/ 600# hvlls. Cmt circ'd to surface. POOH w/tbq. Hooked up to 5 1/2" csg & pumped 45sx of same blend cmt. 75 psig on csg. RIH w/perf gun & perf'd @ 190' (See back of form)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ~~J. W. Gibson Well Service~~ Murfin Drilling License No. ~~5866~~ 30606

Address ~~505 W. Commercial, Logan, KS 67644~~ E. Hwy 24, Box 130, Hill City, KS 67642

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORP. REC-111

9-20-94

SEP 20 1994

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 12th day of September, 1994

[Signature]
 Notary Public

My Commission Expires: 8-21-96