


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-47-20163-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Phillips County, Sec. 31 Twp. 5S Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
1650' FSL - 990' FEL SW NE SE  
Lease Owner Cities Service  
Lease Name Johnson "B" Well No. 9  
Office Address 209 E. William, Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Oil



Locate well correctly on above  
Section Plat

Date Well completed August 16 1973  
Application for plugging filed March 9 1978  
Application for plugging approved March 13 1978  
Plugging commenced April 7 1978  
Plugging completed April 7 1978  
Reason for abandonment of well or producing formation  
Not economical to produce  
If a producing well is abandoned, date of last production  
August 1974

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Reagen Depth to top 3572 Bottom 3574 Total Depth of Well 3574  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	188 ft.	None
				5 1/2"	3572 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Ran 2 1/2" tubing to 3550 ft. Spot 25 sacks gel and 50 sacks  
50-50 Pozmix + 2% gel. Pull tubing. Pump 5 1/2" plug followed with  
95 sacks cement. Filled to surface. P&A Complete at 1:00 p.m.  
4-7-78

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1978

(CONSERVATION DIVISION description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wichita, Kansas Halliburton Oil Cementing Co., Hays, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
E. W. Peterman (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed Glenn E. Meier same are true and correct. So help me God.

STATE NOTARY PUBLIC  
Sedgwick County, Kansas

(Signature) E. W. Peterman E. W. Peterman  
209 E. William, 700 Sutton Pl. Bldg. Wichita,  
(Address) KS 67202

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1978

Glenn E. Meier  
Glenn E. Meier Notary Public.

My commission expires 6-3-81