

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

18-147-00918-00-00

API NUMBER 15-N/A

LEASE NAME Veeh A

WELL NUMBER 11

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

3630 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 31 TWP. 5S RGE. 20 (B) or (x)

COUNTY Phillips

Date Well Completed 10/15/51

Plugging Commenced 2/17/95

Plugging Completed 2/17/95

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/94 (date)

by Herb Deines (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3654 Bottom 3658 T.D. 3658

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3654	3658	8 5/8"	202	
				5 1/2"	3655	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Perf @ 1830' & 1130'. Mixed & pumped 50sks 60/40 pozmix w/10 % gel, 1/4#sk Flocele & 100# hulls. down 8 5/8" - 5 1/2 annulus. Shut-in pressure 50#. Hooked up to 5 1/2" csg pumped 305 sks cmt (same blend) w/ 300# hulls in first 16bbls & 300# hulls in last 150sks. Shut-in pressure 600#. Cut off 5 1/2" csg 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Jerry Ledlow*

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 1st day of May, 1995

Cari Allen
Notary Public

My Commission Expires: 7-14-95

RECORDED
STATE CORPORATION COMMISSION
5-4-95
MAY 6 1995

