

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-00917-00-00  
API NUMBER 15-N/A

LEASE NAME Veeh A

WELL NUMBER 9

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 31 TWP. 5S RGE. 20 (E) or (x)

COUNTY Phillips

Date Well Completed 10/26/49

Plugging Commenced 2/17/95

Plugging Completed 2/17/95

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/94 (date)

by Herb Deines (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3655 Bottom 3659 T.D. 3659

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3655	3659	8 5/8"	203	
				5 1/2"	3654	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Perf @ 1830 & 1130. Mixed & pumped 50sks 60/40 pozmix w/10% gel 1/4# sk Flocele & 100# hulls down 8 5/8" - 5 1/2" annulus. Shut in pressure 50#. Hooked up to 5 1/2" csg. Pumped 305sks cement (same blend) w/300# hulls in first 15bbbls of slurry. Pumped 150# hulls in last 150sks of cmt. Shut in pressure 650# & holding. Cut off 5 1/2" csg 3' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 95

Cari Allen

Notary Public

My Commission Expires: 7-14-95

STATE CORPORATION COMMISSION  
5-4-95  
MAY 04 1995

