

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

15-147-00858-00-00

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 59-11

LOCATION NW NE NE

SEC. 10 TWP. 5 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Graham

Operator Helmerich & Payne Address Box 255 Garden City, Kans

Field _____ County Phillips

Total Depth 3457 Feet.

Plugging Contractor Ace Pipe Pulling & Globe Cementing Co

Plugging Contractor's License No. 2

Address _____

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 160' circulated with cement - 7" 3413' with 200 sax
cement behind - P.B. to 3250' - perforated 3226'

Filled with sand to 3200', set 5 sax cement with dump bailer -

pulled 1425' 7" to 1000', circulated hole with heavy mud (Gel),

displaced 30 sax cement through 7" at 600', heavy mud to 160',

displaced 25 sax cement through 7" at 160', heavy mud to 30', set

rock and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co

E. J. Perry
District Conservation Agent

Date 11-27-57

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1957

CONSERVATION DIVISION
Wichita, Kansas

12-4-57

PLUGGING
FILE SEC 10 T 5 R 20W
BOOK PAGE 59 LINE 11