

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-00491-00-~~XX~~
01

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1971
CONSERVATION DIVISION
Wichita, Kansas
9-28-71

Operator's Full Name Cities Service Oil Company

Complete Address Box 553 Russell, Kansas 67665

Lease Name Vehige "A" Well No. 5

Location C SW NE SW Sec. 28 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3665'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3 P Day 20 Month 9 Year 1971

The above well was plugged as follows:

Total Depth 3665' 8 5/8 csg set at 160' cwc 125 sk.

5 1/2 csg set at 3665' cw 150 sk cmt.

5 1/2 csg PBTD 3598' with top perf. (3334) sk cmt W/dump bailer. (3100-3440)

Filled 5 1/2 csg W/sd (3665-3300) dumped 5 sk cmt W/dump bailer. (3260-3300)

Cutoff and recovered 810' of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water W/400 lbs hulls (900-1660) pumped

70 sk 50-50 poz W/6% gel (610-900) pumped 10 sk gel & water (210-610) released

plug and pumped 50 sk 50-50 poz W/6% gel & 100 lbs hulls. (0-210)

I hereby certify that the above well was plugged as herein stated.

Signed: Geo Massey
Well Plugging Supervisor

INVOICED

DATE 9-29-71

INV. NO. 4379-W