

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 147-20163-00-00 (of this well)

APR 11 1978
4-11-78
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

Operator's Full Name Cities Service Co.
Complete Address 209 East William-700 Sutton Place, Wichita, Kansas 67202
Lease Name Johnson "B" Well No. 9
Location SW NE SE Sec. 31 Twp. 5 Rge. (E) (W) 20
County Phillips Total Depth 3574'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools by Halliburton Cementing Co.
Address License No.
Operation Completed: Hour 1 P Day 7 Month 4 Year 1978

The above well was plugged as follows:

Total Depth 3574' 8 5/8 csg set 186' cwc 175 sk.
5 1/2 csg set 3572' cw 185 sk.
5 1/2 csg 2-stage at 1700' cwc 350 sk. No. pipe recovered.
Circulated 25 sk gel & water at 3450' thru tbg.
displaced 50 sk 50-50 poz 2%. (3450'-3050') thru tbg.
Capped with cementing plug & 75 sk 50-50 poz 2%. (600' to base of cellar.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 4-11-78
INV. NO. 7092-U