

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

SEP 23 1974

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION
Wichita, Kansas
9-23-74

15-147-20176-00-00

Operator's Full Name cities Svc. Oil Co.
Complete Address 209 E. William 700 Sutton Place Bldg. Wichita Ks.
Lease Name Johnson "B" Well No. 11
Location NE-SW-SW Sec. 32 Twp. 5 Rge. 20 (W)
County Phillips Total Depth 3592'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Company- tools-
Address License No.
Operation Completed: Hour 5:00 PM Day 18 Month 9 Year 1974

The above well was plugged as follows:

Sea level Dakota top. +1400 G.I. Elev +2178
8 5/8" surface - 5 1/2" csg cwc to top - No recovery
T.D. 3592 5 1/2" @ 3592 perf-3250-54 3332-84
sanded to 3225' & dumped 4 sacks cement on top-
pushed rubber plug to 900' - Filled to Top
with Redi Mix cement. (J.D. Hieniger.)

I hereby certify that the above well was plugged as herein stated.

Signed: Ralph Balthazor
Well Plugging Supervisor

INVOICED

DATE 9/23/74
INV. NO. 9927-W