

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-19112-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1971
CONSERVATION DIVISION
Wichita, Kansas 630-71

Operator's Full Name Shirer Oil Company,

Complete Address Box #118, Moisington, Kansas.

Lease Name Steele Well No. 1

Location SW-SW-NE Sec. 27 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3580'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 1:30 PM Day 25 Month 6 Year 1971

The above well was plugged as follows:

215'--8 5/8" Surface casing, cement circulated with 160 Sx.
3570'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back. Top perforations from 3556' to 3560'.

Sanded well back to 3525' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2450') and squeezed well with 5 sacks hulls and 14 sacks gel. Pressure just started to build and gained circulation around surface pipe. Ran flag on measuring line and established hole in surface casing @ 20'. Circulated cement thru hole in surface to bottom of cellar with 25 Sx. cement. (Mudding and cementing by Allied).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Nichols
Well Plugging Supervisor

DATE 6/30/71

INV. NO. 3930-W