

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

15-137-00001-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 28 1963
8-28-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name D & D Drilling Company, Inc.,

Complete Address: 308 Schweiter Building, Wichita, Kansas.

Lease Name Williams Well No. 1

Location CSE-SW Sec. 21 Twp. 5 Rge. (E) (W)21

County Norton Total Depth 3681

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Forbes Casing Pulling, Inc.,

Address: Box #221, Great Bend, Kansas. License No. 49

Operation Completed: Hour 12:00M Day 23 Month 8 Year 1963

The Above well was plugged as follows:

240'--8 5/8" Surface pipe, cement circulated. 3678'--5 1/2" casing cemented with 50 Sx.

Sanded well back to 3670' and set 5 Sx cement with dump bailer. Pulled 5 1/2" to 490' and circulated heavy gel mud and displaced 20 Sx cement thru 5 1/2". Pulled 5 1/2" to 230' and displaced 20 Sx cement. Pulled 5 1/2", set plug and ~~and~~ 20 Sx cement to bottom of cellar.

(Cementing and mudding operations performed by Globe Oil Well Cementing Incorporated).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/28/63
INV. NO. 9659-W

Signed: H. D. Nichols
Well Plugging Supervisor