

KANSAS

Form CP-3  
Rev. 6-4-68

*2* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20078-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 15 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
9-13-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address 435 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name Kemper Well No. 1

Location SW-NW-SW Sec. 22 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3681'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.       

Operation Completed: Hour 12:00M Day 13 Month 9 Year 1971

The above well was plugged as follows:

214'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru  
DP from 1075' to 750'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 9-15-71  
INV. NO. 4329-W