

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20009-00-00

RECEIVED
NOV 6 1967
11-6-67
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Howard Alexander,
Complete Address Kennedy Building, Tulsa, Oklahoma.
Lease Name Kemper Well No. 1
Location SW-SE-NE Sec. 22 Twp. 5 Rge. (E) (W) 21
County Norton Total Depth 3592
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Leben Drilling, Incorporated,
Address Box #486, Great Bend, Kansas. License No.
Operation Completed: Hour 10:30PM Day 28 Month 10 Year 1967

The above well was plugged as follows:

216'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1280' to 1495'.

Circulated hole with heavy mud. Pulled DP to 1515' and displaced 100 Sx. cement thru DP.
Pulled DP to 240' and displaced 20 Sx. cement thru DP. Pulled DP, set bridge @ 40'
with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

11/6/67

INV. NO.

6631-W

Signed:

M. L. Nichols
Well Plugging Supervisor