

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00734-00-00

RECEIVED
STATE CORPORATION COMMISSION

AUG 4 - 1965

8-4-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Varn Petroleum Company,

Complete Address: 310 Sutton Place, Wichita, Kansas.

Lease Name Kemper Well No. 1

Location SE-SE-SW Sec. 22 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3625

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box # 562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 6:30PM Day 31 Month 7 Year 1965

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated with 160 Sx. 3619'--5 1/2"
Production casing cemented with 100 Sx.. No Plug back, No Perforations.

Sanded well back to 3610 and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 560' and circulated heavy gel mud (20 Sx. gel). Pulled 5 1/2" to
530 and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 210' and dis-
placed 20 Sx. cement thru 5 1/2". Pulled 5 1/2", set 5' rock bridge @ 35' and
10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/4/65
INV. NO. 1591-W

Signed: A. L. Nichols
Well Plugging Supervisor