

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00621-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 6 1965

CONSERVATION DIVISION
Wichita, Kansas

7-6-65

Operator's Full Name Varn Petroleum Company,

Complete Address: 310 Sutton Place, Wichita, Kansas.

Lease Name Kemper Well No. 2

Location NW-SE-SW Sec. 22 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3676'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box # 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 6:00PM Day 29 Month 6 Year 1965

The Above well was plugged as follows:

209' -- 8 5/8" Surface pipe, cement circulated with 150 Sx.

3676' -- 5 1/2" Production casing cemented with 75 Sx. Well plugged back to 3450'. Top perforations from 3338' to 3344'.

Sanded well back to 3325' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing to 600' and circulated heavy gel mud. Pump pressure built up to 300# before gaining circulation with gel. (used 15 Sx. gel)

Displaced 20 Sx. cement thru 5 1/2" @ 600'. Pulled 5 1/2" to 200' and displaced

20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx.

cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 7-6-65

INV. NO. 1405-W