

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00290-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1970
CONSERVATION DIVISION
Wichita, Kansas

8-17-70

Operator's Full Name D. G. Hansen Trust,

Complete Address Box #187, Logan, Kansas.

Lease Name Noone Well No. 2

Location SW-NW-NW Sec. 18 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3540'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:45 AM Day 13 Month 8 Year 1970

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 140 Sx.
3537'--4 1/2" Production casing cemented on bottom with 125 Sx. No plug back, no perforations.

Sanded well back to 3525' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 100 Sx. cement from 950' to 625' then 10 sacks gel from 625' to 225' and followed with 25 Sx. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Sx. cement from 30' to 0. Maximum pump-in pressure-400#. Final shut-in pressure-200#. (Mudding and cementing operations performed by Halliburton).

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 8/17/70
INV. NO. 2391-W