

⁴⁰
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

15-137-00287-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 20 1964

CONSERVATION DIVISION
Wichita, Kansas
3-20-64

Operator's Full Name Woodman & Iannitti Oil Company,

Complete Address: 714 Union National Building, Wichita, Kansas.

Lease Name Kitzke Well No. 1

Location NW-NW-SE Sec. 16 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3654

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Woodman & Iannitti Drilling Company,

Address: 714 Union National Building, Wichita, Kans. License No. _____

Operation Completed: Hour 8:30AM Day 16 Month 3 Year 1964

The Above well was plugged as follows:

192' -- 8 5/8" Surface pipe, cement circulated with 130 Sx.
Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx cement
thru DP. Heavy mud to 180', set plug with 1/4 sack hulls and displaced 20
Sx. cement thru DP, Heavy mud to 40', set plug with 1/2 sack hulls and 10
Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/20/64
INV. NO. 8834-11

Signed: W. L. Nichols
Well Plugging Supervisor