



19-147-20190-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1975
CONSERVATION DIVISION
Wichita, Kansas
4-28-75

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weber of Abercrombie Drlg. has this

date requested permission to plug the following described well:

Mr. Weber guarantees payment of the plugging fee.

Operator's full Name: Leland R. Baird

Complete Address: Logan, Kansas

Lease Name: States Well No. 1

Location: E/2 SE SE Sec. 10 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3530' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Weber was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 820' thru drill
pipe. Heavy mud to 215' set 20 sk cmt plug thru drill pipe. Heavy mud
to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

P. S. Massey
Conservation Division Agent