



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 7 1967
 11-7-67
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Norwood of Leben Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Bankoff & Leben

Complete Address: Drawer 2479, Tulsa, Oklahoma

Lease Name: States Well No. 1

Location: SW SW NE Sec. 10 Twp. 5 Rge. 20 (E)(W) X

County: Phillips Total Depth 3480 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc
cement.

Very truly yours,

B. F. Messer
 Conservation Division Agent